No.	Items of work	Unit	Quantity	Rate	
				In figures	In words
16	White washing two coats	Sqr.	153·83		
17	Jack arch terrace including plastering ...	,,	28·42		
18	Roofing with 1st class Mangalore tiles on teak reepers.	,,	23·54		
19	Ridging 1st class Mangalore tiles set in mortar and cement pointed.	R.ft.	115		
20	Burnt brick in mortar parapet wall 2½′ high, 1·1/8′ thick including plastering and white washing and coping.	,,	351		
21	Burnt brick in mortar cornice (1′) including plastering and white washing.	,,	351		
22	Flooring with 1st class Mangalore tiles on 3″ concrete and cement pointed.	Sqr.	32·96		
23	Providing and fixing teakwood ornamental eave boards 9″ x 1″ including chocolate painting.	R.ft.	151		
24	Zinc white painting 2 coats	Sqr.	18·20		
25	Cement pointing after scraping joints ...	,,	12·45		
26	Ornamental teakwood large board for darmar including chocolate painting.	L. S.	Rs.		
27	Providing 5′ zinc sheets for valleys ...	R.ft.	56		
28	Do water connection to bath and water closet.	L. S.	Rs.		
29	Do sinks do do ...	No.	6		
30	Do mortar band including cement plastering.	R.ft.	165		
31	Cutting grooves in cill slabs for door posts ...	No.	40		
32	Providing zinc sheet down pipes 4″ dia. ...	R.ft.	150		
33	U. shaped drain alround the building with brick in surki mortar and cement plastered.	L. S.	Rs.		
34	Levelling ground, forming approach road with culvert, etc.	L. S.	Rs.		
35	Boxing girders with cement concrete ...	C.ft.	94		

Abstract Notification.

The attention of the public is invited to the notice calling for tenders for improving Rayakalve of Madag tank published in pages 121 and 123 of Part VI of the *Mysore Gazette*, dated 30th January 1930. The last day for receiving tenders is 18th February 1930 till 3 P.M.

Abstract Notification dated 16th January 1930.

The attention of the public is invited to the notice calling for tenders for constructing quarters for the Executive Engineer at Chikmagalur on pages 96 to 98, of Part VI, of the *Mysore Gazette*, dated 23rd January 1930.

The last date for receiving tenders is 8th February 1930 at 2 P.M.

L. A. H. WINCKLER,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification.

The attention of the public is hereby invited to the advertisement page No. 124 of the *Mysore Gazette* of dated 30th January 1930, calling for tenders for the work of Restoring Malakere (Sannakere) R. No. 32 of Davangere Taluk.

Notice dated 9th January 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 25th February 1930, for the construction of a Dispensary Building at Rampur Molakalmuru Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates, at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 250 in cash or Currency Notes as earnest money and be superscribed "Tender for the construction of a Dispensary Building at Rampur, Molakalmuru Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract of quantities for the construction of a dispensary building at Rampur, Molakalmuru Taluk.

Serial No.	Names of items	For	Quantity
1	Earthwork excavation	C.yd.	78
2	Concrete foundation	C.ft.	620
3	Burnt stone in mortar	"	1,968
4	Burnt brick in clay	"	2,017
5	Burnt brick in mortar	"	555
6	Chunam plastering	Sqr.	51·30
7	White washing two coats	"	52·25
8	Burnt stone slabs 6" thick dressed and fixed	S.ft.	279
9	Coping with brick in clay and chunam plastering ...	R.ft.	42
10	Teakwood work wrought and put up with wood oiling ...	C.ft.	1,017
11	Teakwood panelled doors with fittings clamps lock, etc., complete.	S.ft.	77
12	Teakwood panelled windows in two halves outside and glazed inside with iron bars, clamps and fittings, etc., complete.	"	20
13	Teakwood panelled window with iron bars and fittings complete.	"	5
14	Teakwood panelled shelves with glazed shutters ...	"	72
15	Silicate painting two coats	Sqr.	11 62
16	Ornamental Eave Board	Rft.	144
17	Roofing with first class Mangalore tiles and teak reepers, etc., complete.	Sqr.	16·45
18	Ridge tiles set in mortar	R.ft.	87
19	Providing ventilating tiles	No.	4
20	Flooring with 9" x 9" Mangalore tiles on 3" concrete and cement pointing.	Sqr.	8·40
21	Flooring with 3" concrete and cement plastering with V shaped drain, etc., complete.	"	4·13
22	Pointing to basement with cement	"	31
23	Providing sinks with outlets	No.	2
24	Do teakwood wall boards one foot wide with supports.	S.ft.	34
25	Chunam borders	R.ft.	28
26	Earth filling to basement with consolidation	C.yd.	79
27	Providing teakwood screen	S.ft.	48
28	Do and fixing teakwood gate	"	13
29	Do teakwood pendants	Each	10
30	Clearing site and levelling ground and sundry items, etc. ...	Lump sum	
31	Constructing brick in chunam seats over concrete bed and cement plastering and also to a height of one foot for the inside walls alround.	"	"
32	Constructing a cistern outside with 4½" thick brick walls and cement plastering complete.	"	"